


203-15.

# The Johns-Manville Underground System of Insulation


*Heat*



This successful installation by  
Johns-Manville Incorporated  
of an underground system of  
pipe insulation and distribu-  
tion from a central power  
house demonstrates the flexi-  
bility and economy of such a  
system.



A  
Representative Installation of the  
Johns-Manville  
Underground System of Insulation



MCMXXIV  
JOHNS-MANVILLE INCORPORATED  
NEW YORK



Birdseye view of the extensive campus at Cornell University

## The Johns-Manville Underground System of Insulation

THE achievement of maximum economy in central heating and power plants for the distribution of steam and hot water to building units of institutions and industrial plants has been assisted by a system of distribution, scientifically engineered and insulated according to accepted practice. This system has developed, on test, efficiencies over 90%.

The system consists not only of the parts shown in the plate on page sixteen, such as iron roll frames, specially designed vitrified tile, Asbesto-Sponge insulation, man-hole pits and other units, *but the assembling of these units into a complete system* installed by Johns-Manville Inc.

As will be later developed, the saving effected by the centralization of heating plants is further increased when the steam is distributed through the Johns-Manville Underground System of Insulation.

A few years ago the authorities of Cornell University, with the desire to heat the entire institution as economically as possible, decided to replace a number of small heating plants and low-pressure house heating boilers with one large central heating plant; and to replace numerous small concrete tunnels and other types of underground conduit with a better and more efficient system for enclosing and insulating underground steam pipes.

In preparing plans and specifications for an underground system of insulation the University authorities stipulated that the efficiency obtained upon completion must be not less than 90%. The Johns-Manville Underground System of Insulation was finally decided upon and the contract let.

The following information is given so that those considering the use of an underground system of insulation will have some idea of the various steps in its assembly





and construction and what has been accomplished through the installation of this system at Cornell:

Plans and specifications were prepared for the installation of an entirely new system. The new plant was designed for five 612 h. p. boilers to give a capacity of 5,500 b. h. p. Upon completion the loss through insulation on the steam mains was not to exceed 10% and on the return mains not more than 15% of the loss from bare pipe, based on a condensation test to be conducted when the operation was finished.

Over 19,400 feet of underground conduit lines were installed. Almost every character of ground condition was encountered, such as rock, quicksand, moisture, roads, and deep and shallow trenches.

Batter-boards were erected to insure perfect alignment, paralleling the lines from which measurements for ditching and laying the conduit were made. The bell and spigot open joint underdrains were placed in sub-trenches at the bottom of the conduit trenches. The bottom halves of the conduit were then laid on a gravel bed, and at 12-foot centers roll frames, with rollers to allow for the steam pipe expan-

sion, were set in concrete piers. The piping was then lowered onto the roll frames and all joints welded. After the piping had been subjected to a hydrostatic test, the top sections of the tile-containing members were applied. As each successive top was set and cemented in place the entire space between the steam piping and the container was filled with Johns-Manville Asbesto-Sponge Conduit Filling. All joints were waterproofed with Johns-Manville Asphalt Roof Coating. The gravel bed was then brought up above the side joints of the tile-containing members and the trench backfilled to grade.

The underground work on the main contract was completed September, 1922.

The condensation test to determine the efficiency of the installation was made 13 months later. The results are given on page fourteen.

Johns-Manville Inc. takes pride in the list of representative installations on pages eighteen, nineteen and twenty. It will be noted that some of the foremost institutions and industrial plants of the country are represented. They stand as permanent testimonials to the Johns-Manville Underground System of Insulation.





Main thoroughfare between athletic field and drill hall. Agricultural buildings are seen in background. All are heated by the new plant and system. In the center foreground, trenching machine is shown digging trench for Johns-Manville Underground System of Insulation.



Heating plant site; coal trestle and foundation walls erected. Forms for tunnel from heating plant to creek are shown near shack on the right. Foundation for heating plant in center.





Showing the steel work and coal bunkers for power plant in place.




Creek from which make-up water is pumped to heating plant—a distance of about 100 feet. Tunnel excavation is seen near frame building at right. The 12-inch steam and 8-inch return mains are run through this tunnel thence overhead across the stream and on piers, carrying the expansion bend, to a point beyond the trees where they again enter the ground.





Showing boom and bucket of trenching machine loading truck with dirt. Excavation in the foreground is for a large expansion manhole. Conduit lines from heating plant run through trench in which men are working. This also shows another ground condition encountered.



Conduit trench and large double offset expansion loop chamber being sunk near the athletic field. Trench is shown in immediate foreground. At right are materials awaiting installation.





One of the numerous difficult conditions encountered. Many springs and some quicksand gave considerable trouble during ditching work. The trench varied in depth from 3 to 25 feet.



The mechanic is laying the underdrain in the sub trench made for this purpose. Two underdrains are laid because of two runs of conduit. Grades are established by measuring downward from the overhead parallel batter-boards.




Diagram showing construction details of the system.






Showing the lower half of the conduit being laid, the mechanic measuring for proper grade from line above. Note that conduit is laid in gravel through which rain or spring water rapidly percolates to the underdrain.



Centering lower half of conduit by means of a suspended plumb-bob. The iron pipe standing against trench to the left of the mechanic is used to ram gravel under the conduit thus providing a substantial bed.



Detail showing conduit entering through building foundation, trench, underdrain, gravel bed and bottom half of conduit. Note perfect alignment of the line.



Mechanic setting roll frames in concrete piers. These frames support the piping.





This is the way roll frames are set to proper elevation. Measurements are made for all units in the Johns-Manville System by measuring from the overhead line to the unit being installed.



Installation showing Johns-Manville four roll frame unit. This type provides for double-deck construction.




Piping being installed on roll frames. Joints are being welded. An 8-inch steam line and two 6-inch return lines are shown. Expansion chamber in background.



Conduit tops being applied. The upper and lower halves are numbered so they can be properly mated. Conduit filling is seen beneath the piping.





Two clear views showing the 12-inch high pressure steam and 8-inch return piping rising to the top of a very steep hill from a point near where they enter the ground, a short distance from the heating plant. At this point the conduit lines were laid practically at the surface of the ground. The grade was brought up higher upon completion of the installation. The two-by-fours at sides are used to line up the pipe during welding and are removed before top halves are applied. The small view shows the tops applied and the trench ready for backfill.





After each top is set, the space between it and the pipe is rammed to proper density with Johns-Manville Asbesto-Sponge Conduit Filling. This method fills the entire conduit and thus prevents air circulation.



After a number of top halves are applied the bell joints are thoroughly cemented.



Mechanics waterproofing exposed cement surfaces.



Next to the last operation. Placing additional gravel in trench to bring it above side-joints. This is followed by backfilling and grading.





Double run of completed conduit ready for waterproofing, additional gravel and backfill. This run is under a roadway between Drill Hall and Athletic Field. The picture on page five shows this during construction.



# Condensation Test

92.77% efficiency shown at Cornell University

THE test to determine the efficiency of the installation was conducted by William M. Sawdon, Professor of Experimental Engineering at Cornell University. The owner provided and installed proper steam connections with stop valve, steam calorimeter and connections for pressure gauge and thermometers to measure the temperature of the steam; suitable arrangements for collecting condensation; and thermometers for taking soil temperatures.

The purpose of this test was to prove the guarantee which the specification stated as follows:

Loss of heat from steam pipes under test shall not exceed 10% of what the loss would be in a corresponding bare pipe exposed in still air where the temperature of the air is the same as that of the ground. The loss of heat from bare pipe in still air shall be figured according to a curve plotted to the following:

Temp. diff. deg. Fahr. between pipe and still air	Heat loss in B.t.u. per sq. ft. of exterior pipe area per deg. Fahr. temp. diff. per hr.
50	1.95
100	2.152
150	2.4
200	2.665
250	2.951
300	3.26
350	3.627
400	4.035
450	4.557
500	5.18

The test was conducted on the major portion of the steam line running from manholes F to M,

M to P<sub>1</sub> and M to BB (see plot plan, page 3) which consisted of the following insulated pipe in conduit and manholes:

1832 ft. of 10" pipe in 18" conduit	} Stations F to M
72 ft. of 10" pipe in manholes ..	
2316 ft. of 8" pipe in 15" conduit	} Stations P <sub>1</sub> to X
149 ft. of 8" pipe in manholes ..	
434 ft. of 6" pipe in 15" conduit	} Stations X to AA
4 ft. of 6" pipe in manholes ..	
10 ft. of 5" pipe in manholes ..	
227 ft. of 5" pipe in 12" conduit	} Stations AA to BB
3 ft. of 5" pipe in manholes ..	

5047 ft. total length of pipe in conduit and manholes under test, exclusive of fittings and expansion joints which were also included in test.

The test in general consisted of supplying steam to the portion of the line under test, which was closed off from the remainder of the system, and collecting and weighing the water of condensation at three low points in the line. The pressure on the test line was maintained constant through a pressure-reducing valve. Periodic readings were taken of the pressure and the quality of the steam supplied. Half-hourly readings were taken of the temperatures in all manholes, at five points in the ground, and of the outside air. Every precaution was taken to secure accurate, simultaneous readings at all stations. The test was complete when constant readings had been obtained over a period of six hours.



The following tabulation gives a summary of the data, and results obtained from the test:

### Data

Date of test .....	October 7, 1923
Weather .....	Clear
Duration of test .....	6 hours
Barometer pressure .....	29.52 inches
Average temperature outdoors	55 deg. Fahr.
Average temperature in manholes .....	124 deg. Fahr.
Average temperature of ground 50 feet or more from conduit .....	58 deg. Fahr.
Average steam pressure, gauge .....	139.0 lbs.
Average steam pressure, absolute .....	153.5 lbs.
Average steam temperature...	360 deg. Fahr.
Average quality of steam supplied .....	98.9%
Total weight of condensate collected per hour.....	1327.5 lbs.
Weight of steam condensed per hour .....	1312.9 lbs.
Latent heat of 1 lb. steam at 153.5 lbs. pressure.....	861.7 B. t. u.
Difference in temperature between steam in pipe and surrounding earth .....	302 deg. Fahr.
Area of insulated pipe between manholes .....	11,470.8 sq. ft.
Area of insulated pipe and fittings in manholes.....	1,006.8 sq. ft.
Total area of insulated pipe and fittings .....	12,477.6 sq. ft.
Area of bare pipe and fittings in manholes.....	387.7 sq. ft.

### Results

Heat loss per hour equivalent to steam condensed.....	1,131,500 B. t. u.
Heat loss per hour by bare surfaces in manholes.....	262,660 B. t. u.
Net heat loss per hour from insulated surfaces under test	868,840 B. t. u.

### CALCULATED HEAT LOSS PER HOUR FROM EQUIVALENT BARE SURFACE IN STILL AIR:—

Insulated pipe between manholes .....	11,327,870 B. t. u.
Insulated pipe and fittings in manholes .....	694,640 B. t. u.
Total heat loss per hour from equivalent bare surface in still air .....	12,022,510 B. t. u.
Net heat loss per hour from insulated surfaces (see result col.) .....	868,840 B. t. u.
Heat saving per hour =	11,153,670 B. t. u.
Efficiency = $\frac{\text{Heat saved per hour by insulation}}{\text{Heat loss per hour from equivalent bare surface in still air.}}$	
	$= \frac{11,153,670}{12,022,510} \times 100\% = 92.77\%$
Heat Loss =	$100\% - 92.77\% = 7.23\%$

### Conclusions


This test proved that the Johns-Manville Underground System of Insulation (consisting of insulated piping and fittings in conduit and manholes) *exceeded the guarantee, in that the heat loss was only 7.23% of the bare pipe loss, whereas the specification allowed a loss of 10%.* This means that the actual loss from the Underground System of Insulation which had been installed for 13 months, and in operation for the greater part of that time, was 2.77% lower than the loss allowed by the guarantee. This represents an *additional* saving of 85 tons of coal annually over and above the guaranteed saving *on the tested portion alone* (based on operation eight months of the year).

The plant is now operating for its second successful heating season and is reported as giving entirely satisfactory results.

As all the materials used for insulating purposes in this installation, and the waterproof envelope protecting the insulation, i.e. tile, asbestos and iron roll frames, are practically indestructible, the high insulating efficiency will, with little attention, be maintained during the life of the system.



# Integral parts of the Johns-Manville System



The integral parts of the Johns-Manville Underground System of Insulation:  
1—straight section; 2—supporting section; 3—manhole frame; 4—door-frame frame.



# Description of the Johns-Manville System

**T**HE Johns-Manville Underground System of Insulation provides a permanent, efficient and economical means of placing underground and insulating pipes conveying steam or hot water.

The system comprises not only the integral parts shown on the opposite page, but the proper selection and arrangement of these parts and the installation or supervision of installation of them by Johns-Manville engineers.

The average efficiency of the Johns-Manville System is at least 90% when installed according to our specifications and by us or under our supervision. This high efficiency is maintained for a long period of time on account of the character of the materials used in construction.

The high and lasting heat insulating efficiency of Johns-Manville Asbesto-Sponge Filling is due to the many "dead air" spaces and cells which it confines, and to its base of indestructible asbestos fibre. When packed around the pipe to be insulated, it completely fills the space inside of the protecting and containing members of the system. It is extremely resilient and spongy, so that there is little tendency for it to settle.

The Johns-Manville Supporting Roll Frame has been designed to provide support for the pipes and to insure that they may move freely when expanding and contracting.

The Supporting Section of the system is a most important part as it completely covers and encloses the roll frames and also acts as a connecting link between the containing sections.

The supporting sections are connected by Containing Sections, which complete the continuous stone protective member which surrounds the entire system and acts as a container for the Asbesto-Sponge Filling.

The sections are split diagonally, so that the lateral joints will shed water better than if the cut of the joint were straight, and each half of every section is numbered so that in the installation of the system mates of each section will always be placed together.

Provision is made to prevent water from accumulating around the system and to drain or carry it away by the use of an Underdrain of small tile pipe laid with open joints and embedded in crushed stone, which is carried up and around the system to a point above the lateral joints.

Wherever there may be valves, expansion joints, flanged joints, or other features which it may be desirable or necessary to reach occasionally, and which cannot be placed in a building into which the system runs, a manhole with a removable but water-tight cover should be employed.

## *Berea College and Allied Schools*

Heat and Power Plant  
George G. Dick, Supt.

Berea, Ky., May 16, 1924.

Johns-Manville Inc.,  
New York City.

Gentlemen:—

The other day we had occasion to make a steam tap in one of our low pressure steam conduit mains. This conduit line, which is made of Johns-Manville sectional conduit and filled with your Asbesto-Sponge filler, was installed 20 years ago and you will be interested to know that the Asbesto-Sponge filler had not settled over one-quarter of an inch, was perfectly dry, and seemingly in as good condition as it was the day we installed it. The pipes are also in fine condition.

We have not spent a penny on this underground steam main for repairs during these 20 years. We anticipate many more years of service from this, our oldest steam conduit line.

The line was put in under the supervision of the R. D. Kimball Company of New York City.

We are glad to be able to send you such a favorable report and believe you will be glad to know these facts.

Very truly yours,

(signed) Geo. G. Dick.



# Representative Installations

## ALABAMA

West Point Mfg. Co. . . . . Fairfax  
Boys School . . . . . East Lake  
Alabama Masonic Home . . . . . Montgomery

## ALASKA

Alaskan Engineering Commission . . . . . Anchorage

## ARKANSAS

State Agricultural School . . . . . Russellville

## CALIFORNIA

Danziger residence . . . . . Beverly Hills  
Civic Center . . . . . San Francisco  
Stanford Jr. University . . . . . Stanford

## CANADA

McGill University . . . . . Montreal, Que.  
Canadian Pacific Railway . . . . . Montreal, Que.  
Canadian Products, Ltd. . . . . Windsor, Ont.  
Canadian Sugar Refining Co., Ltd. . . . . Montreal, Que.  
Imperial Tobacco Co. . . . . Montreal, Que.  
Imperial Tobacco Co. . . . . Granby, Que.  
St. Maurice Pulp and Paper Co. . . . . Three Rivers, Que.  
Normal School . . . . . Granby, Que.  
General Motors . . . . . Oshawa

## COLORADO

Colorado Springs Elec. Co. . . . . Colorado Springs  
United Service Co. . . . . Colorado Springs  
Pueblo Elec. Co. . . . . Pueblo

## CONNECTICUT

Hartford Retreat . . . . . Hartford  
Pratt & Whitney . . . . . Hartford  
Waterbury Hospital . . . . . Waterbury  
Westover School . . . . . Middletown  
Torrington Hospital . . . . . Torrington  
Edward Malley . . . . . New Haven  
Norwich Insane Hospital . . . . . Norwich  
Scoville Mfg. Co. . . . . Waterbury  
Thread Agency . . . . . Willimantic  
Wesleyan University . . . . . Middletown  
Connecticut School for Feeble Minded . . . . . Mansfield  
Connecticut Colony for Epileptics . . . . . Mansfield  
Taft School . . . . . Watertown  
American Brass Co. . . . . Ansonia  
Wm. Ziegler residence . . . . . Noroton  
American Brass Co. . . . . Waterbury  
Franklin S. Jerome residence . . . . . Greenwich

## DELAWARE

American Vulcanized Fibre Co. . . . . Newark  
Winterthur Farms . . . . . Winterthur

## DISTRICT OF COLUMBIA

U. S. Dept. of Agriculture . . . . . Washington

## FLORIDA

Florida East Coast Hotel . . . . . Palm Beach

## GEORGIA

Atlanta Baptist College . . . . . Atlanta  
State Agricultural School . . . . . Athens

## IDAHO

Oregon Short Line Ry. . . . . Pocatello

## ILLINOIS

Bolton Bros. Electric Co. . . . . Aledo  
Liquid Carbonic Co. . . . . Chicago  
University of Illinois . . . . . Champaign  
American Bridge & Iron Co. . . . . Chicago  
Illinois Malleable Iron Co. . . . . Chicago  
Lincoln Park . . . . . Chicago  
Municipal Tuberculosis Sanitarium . . . . . Chicago  
Star Mfg. Co. . . . . Carpentersville  
Elgin, Joliet & Eastern R. R. . . . . East Joliet  
N. Y. C. R. R. Company . . . . . Englewood  
Residence of Mrs. C. H. McCormick . . . . . Lake Forest  
Barber Coleman Co. . . . . Rockford  
St. Charles School for Boys . . . . . St. Charles  
Southern Illinois State Normal School . . . . . Carbondale

## INDIANA

Northern Ind. Hospital for the Insane . . . . . Long Cliff  
Oliver Chilled Plow Co. . . . . South Bend  
Dodge Mfg. Co. . . . . Mishawaka  
M. Rumely Co. . . . . La Porte  
Notre Dame University . . . . . South Bend  
Studebaker Co. . . . . South Bend  
Lake Shore & Michigan Southern Ry. . . . . South Bend  
Claypool Hotel Co. . . . . Indianapolis  
St. Joseph's College . . . . . Rensselaer  
Republic Iron & Steel Co. . . . . East Chicago  
Western Drop Forge Co. . . . . Marion  
City Water & Electric Co. . . . . Mishawaka  
La Porte Gas & Electric Co. . . . . La Porte  
Marion Branch, N. H. D. V. S. . . . . Marion

## IOWA

Iowa College . . . . . Grinnell  
Municipal Electric Light, Heat &  
Power Co. . . . . Ackley  
G. E. Reed . . . . . Davenport  
Carr-Ryder Adams Co. . . . . Dubuque  
People's Gas & Electric Co. . . . . Mason City



## KENTUCKY

Berea College . . . . . Berea  
Western Kentucky Asylum for Insane . Hopkinsville

## KANSAS

Washburn College . . . . . Topeka

## MAINE

University of Maine . . . . . Orono  
Grand Trunk Railway . . . . . Portland

## MASSACHUSETTS

International Y. M. C. A. College . . . Springfield  
Amherst College . . . . . Amherst  
Mt. Holyoke College . . . . . So. Hadley  
Groton School . . . . . Groton  
Mass. Agricultural College . . . . . Amherst  
Mt. Hermon School . . . . . Mt. Hermon  
Northfield Seminary . . . . . Northfield  
Phillips Academy . . . . . Andover  
Abbot Academy . . . . . Andover  
Wellesley College . . . . . Wellesley  
Williams College . . . . . Williamstown  
Charles River Basin Co. . . . . Cambridge  
Vacuum Oil Co. . . . . East Cambridge  
Middlesex School . . . . . Concord  
Boston State Hospital . . . . . Dorchester  
Grafton State Hospital . . . . . Grafton  
Newton Theological Seminary . . . . . Newton  
Holy Cross College . . . . . Worcester  
St. Michael's Cathedral and School  
Association . . . . . Springfield  
Wheaton College . . . . . Norton  
Mass. Hospital for Epileptics . . . . . Palmer  
Danvers Insane Asylum . . . . . Danvers  
Mary McClellan Hospital . . . . . Cambridge

## MICHIGAN

Lake Superior Steam Heating Co. . . Iron Mountain  
Detroit United Railways Co. . . . . Detroit  
Battle Creek Sanitarium . . . . . Battle Creek

## MINNESOTA

Alexandria Heating Co. . . . . Alexandria  
City of Buhl Municipal Buildings . . . . . Buhl

## MONTANA

Montana State Hospital for the  
Insane . . . . . Warm Springs  
State Agricultural School . . . . . Bozeman  
Bozeman University . . . . . Bozeman  
House of the Good Shepherd . . . . . Helena  
State Hospital . . . . . Warm Springs

## NEW HAMPSHIRE

New Hampshire College . . . . . Durham  
Dartmouth College . . . . . Hanover  
Phillips Exeter Academy . . . . . Exeter  
Proctor Academy . . . . . Andover  
City of Franklin Municipal Buildings . . . Franklin

## NEW JERSEY

E. R. Squibb & Co. . . . . New Brunswick  
P. Ballantine & Co. . . . . Newark  
Jacques Wolf & Co. . . . . Passaic  
Celluloid Co. . . . . Newark  
Public Service Corporation . . . . . Newark  
Monmouth Memorial Hospital . . . . Long Branch  
Montclair School . . . . . Montclair  
Estate of H. McK. Twombly . . . . . Madison  
New Jersey State Home for Girls . . . . Trenton  
U. S. Govt. Proving Grounds . . . . . Sandy Hook  
Eastwood Wire Mfg. Co. . . . . Belleville  
Eastern Coal Dock Co. . . . . South Amboy  
Manhattan Rubber Mfg. Co. . . . . Passaic  
Long Branch School . . . . . Long Branch  
Baker Castor Oil Co. . . . . Jersey City  
Morris Avenue School . . . . . Long Branch  
Tuberculosis Preventorium . . . . . Farmingdale  
Boonton Rubber Co. . . . . Boonton  
Montclair Normal School . . . . . Montclair  
Singer Mfg. Co. . . . . Elizabethport  
Standard Underground Cable Co. . . . Perth Amboy  
Merek & Co. . . . . Rahway  
Stevens Institute of Technology . . . . Hoboken  
St. Mary's Hospital . . . . . Orange  
Drew Theological Seminary . . . . . Madison  
East Orange High School . . . . . Orange  
St. Joseph's Hospital . . . . . Paterson

## NORTH CAROLINA

A. & M. College . . . . . Raleigh

## NEW YORK

Municipal and County Buildings . . . New York City  
Metropolitan Hospital . . . . . Blackwell's Island, N. Y. C.  
U. S. Navy Yard . . . . . Brooklyn  
Union College . . . . . Schenectady  
General Electric Co. . . . . Schenectady  
Manhattan State Hospital . . . . . Ward's Island, N. Y. C.  
U. S. Government Arsenal . . . . . Watervliet  
H. L. Pratt residence . . . . . Glen Cove  
Masonic Home . . . . . Utica  
N. Y. Orthopaedic Hospital . . . . . White Plains  
Niagara Falls High School . . . . . Niagara Falls  
Fordham Hospital . . . . . New York City  
Burke Relief Foundation . . . . . White Plains  
H. W. Boettger residence . . . . . Riverdale  
Metropolitan Life Insurance Co. . . . Mt. McGregor  
Mrs. Gordon K. Bell residence . . . . . Katonah  
Borden's Condensed Milk Co. . . . . Brewster  
Long Island State Hospital . . . . . Brooklyn  
Fredonia Normal School . . . . . Fredonia  
Jacob Zoller Co. . . . . Little Falls  
Troy Orphan Asylum . . . . . Troy  
Central Union Gas Co. . . . . New York City  
Weber Electric Co. . . . . Schenectady  
C. O'D. Iselin . . . . . New Rochelle  
Lawrence Park Light, Heat & Power  
Company . . . . . Bronxville  
Hebrew Sheltering Society . . . . . Pleasantville  
The Castle School . . . . . Tarrytown  
Colgate University . . . . . Hamilton

Continued on next page



## NEW YORK—Continued

Wells College . . . . . Aurora  
 University of Rochester . . . . . Rochester  
 Bloomingdale Hospital . . . . . White Plains  
 New York State Reform School for  
 Girls . . . . . Bedford Hills  
 New York State Agricultural  
 College . . . . . Farmingdale, L. I.  
 New York State Hospital . . . . . Gowanda  
 New York State School for Girls . . . . . Hudson  
 St. Stephen's College . . . . . Anandale  
 Letchworth Village . . . . . Thiells  
 Central Islip State Hospital . . . . . Central Islip  
 City Farm Colony . . . . . Staten Island  
 Louis C. Tiffany residence . . . . . Oyster Bay  
 Cathedral of St. John the Divine . . . . . New York City  
 Mrs. Whitelaw Reid residence . . . . . White Plains  
 Samaritan Hospital . . . . . Troy  
 Astoria Light, Heat & Power Co. . . . . Astoria, L. I.  
 General Vehicle Co. . . . . Long Island City  
 St. Lawrence State Hospital . . . . . Ogdensburg  
 Faxton Hospital . . . . . Utica  
 New York Public Library . . . . . New York City  
 New York State Soldiers' Home . . . . . Bath  
 Lakeside School . . . . . Spring Valley  
 Vassar College . . . . . Poughkeepsie  
 Vassar Brothers Hospital . . . . . Poughkeepsie  
 Cornell University . . . . . Ithaca  
 Wingdale Prison . . . . . Wingdale  
 Halcomb Steel Co. . . . . Syracuse  
 Sing Sing Prison . . . . . Ossining  
 Capt. De Lemar residence . . . . . Glen Cove, L. I.  
 Utica Knitting Co. . . . . Utica  
 E. F. Albee residence . . . . . Larchmont  
 Jewish Pro. Aid Society . . . . . Hawthorne

## OHIO

People's Light, Heat & Power Co. . . . . Springfield  
 City of Cleveland . . . . . Brookside Park  
 Corrigan, McKinney & Co. . . . . Cleveland  
 Oberlin College . . . . . Oberlin  
 Institute for Feeble Minded . . . . . Morgens  
 Ohio Cultivating Co. . . . . Bellevue  
 Cleveland Foundry Co. . . . . Cleveland  
 American Textile Co. . . . . Greenfield  
 Cuyahoga County Court House . . . . . Cleveland  
 City of Cleveland . . . . . Cleveland  
 Western Automatic Machine Screw Co. . . . . Elyria  
 Toledo Furnace Co. . . . . Toledo

## PENNSYLVANIA

United Gas Improvement Co. . . . . Philadelphia  
 Wayne Elec. Light & Steam Heat Co. . . . . Wayne  
 Penn. Institution for the Deaf and Dumb . . . . . Mt. Airy  
 Vanadium Hotel . . . . . Cambridge Springs  
 White Haven Sanitarium . . . . . White Haven  
 Muhlenberg College . . . . . Allentown  
 Presbyterian Home . . . . . Bala  
 Church of the Redeemer . . . . . Bryn Mawr  
 Lafayette College . . . . . Easton  
 Elliot Co. . . . . Jeannette  
 Pennsylvania Reform School . . . . . Morganza  
 Church of Gesu . . . . . Philadelphia

Church of Nativity . . . . . Philadelphia  
 Elizabeth Steel Magee Hospital . . . . . Pittsburgh  
 P. H. Glatfelter . . . . . Spring Grove  
 Swarthmore College . . . . . Swarthmore  
 Central Station for the Town of  
 Windber . . . . . Windber  
 State Normal School . . . . . Indiana

## RHODE ISLAND

St. Mary's Church Parish . . . . . Providence  
 The Brown & Sharp Mfg. Co. . . . . Providence  
 R. I. School for Feeble Minded . . . . . Exeter  
 State Hospital . . . . . Howard  
 Church of Our Lady of Good Counsel . . . . . Phoenix

## SOUTH DAKOTA

State School of Mines . . . . . Rapid City  
 Mobridge Electric Light, Power and  
 Heating Co. . . . . Mobridge

## TENNESSEE

University of Tennessee . . . . . Chattanooga  
 Nashville Gas and Heating Co. . . . . Nashville

## UTAH

Oregon Short Line . . . . . Salt Lake City

## VERMONT

Middlebury College . . . . . Middlebury  
 Vermont Hospital for Insane . . . . . Waterbury  
 Brattleboro Retreat . . . . . Brattleboro

## VIRGINIA

A. J. Kennard . . . . . Roanoke  
 Hampton Normal & Agricultural  
 Institute . . . . . Hampton

## WASHINGTON

University of Washington . . . . . Seattle  
 Tacoma Gas Co. . . . . Tacoma

## WEST VIRGINIA

West Virginia Wesleyan College . . . . . Buckhannon  
 West Virginia Colored Institute . . . . . Institute  
 University of West Virginia . . . . . Morgantown  
 Welch Miners Hospital . . . . . Welch  
 Eagle Glass & Mfg. Co. . . . . Wellsburg

## WISCONSIN

Chicago Brass Co. . . . . Kenosha  
 Dodge County Insane Asylum . . . . . Juneau  
 Milwaukee County Almshouse . . . . . Wauwatosa  
 Wisconsin Condensed Milk Co. . . . . Burlington  
 Cedar Island Lodge . . . . . Lake Nebagamon  
 St. Francis Seminary . . . . . St. Francis  
 Kemp Smith Mfg. Co. . . . . West Allis  
 St. Johns R. C. Church . . . . . Jefferson

## WYOMING

University of Wyoming . . . . . Laramie



## JOHNS-MANVILLE

Incorporated

Executive Offices: New York

Akron  
Albany  
Atlanta  
Baltimore  
Birmingham  
Boston  
Buffalo  
Charleston, W. Va.  
Chicago  
Cincinnati  
Cleveland  
Columbus  
Dallas  
Dayton  
Denver  
Detroit  
Duluth  
Erie  
Grand Rapids

Houston  
Huntington  
Indianapolis  
Kansas City  
Los Angeles  
Louisville  
Memphis  
Milwaukee  
Minneapolis  
Nashville  
Newark  
New Orleans  
Omaha  
Philadelphia  
Pittsburgh  
Portland, Me.  
Portland, Ore.  
Providence

Rochester  
Salt Lake City  
San Diego  
San Francisco  
Seattle  
St. Louis  
St. Paul  
Springfield, Mass.  
Syracuse  
Tacoma  
Toledo  
Tulsa  
Washington  
Wilkes-Barre  
Worcester  
Youngstown  
Havana, Cuba  
Rio de Janeiro, Brazil  
Sao Paulo, Brazil

Canadian Johns-Manville Co., Ltd.

Montreal

Vancouver

Ottawa

Winnipeg

Toronto





# **The Johns-Manville Underground System of Insulation**

